

ADDENDUM NO. 1

2 PAGES

TO: BIDDERS AND SUPPLIERS FOR
**FRIDAY HARBOR HIGH SCHOOL TURNBULL
STEM BUILDING ART CLASSROOM**
FRIDAY HARBOR, WASHINGTON

FROM: HKP ARCHITECTS, PLLC
204 WEST MONTGOMERY STREET
MOUNT VERNON, WA 98273
PHONE: (360) 336-2155

TO ALL BIDDERS AND SUPPLIERS:

THIS ADDENDUM SHALL BE ATTACHED TO THE INSIDE COVER TO
THE PROJECT MANUAL AND BECOME A PART OF THE TERMS OF
THE CONTRACT DOCUMENTS. ACKNOWLEDGE RECEIPT OF
ADDENDUM ON THE FORM OF BID.

A. IMPORTANT NOTICE

1. None.

B. GENERAL COMMENTS

1. Walk-through: A non-mandatory pre-bid walk-through will be held on Tuesday, February 7 and Thursday, February 9 at 10:30 am at the site.
2. Addendum Number 002 will be issued Tuesday, February 14 with information discussed at the pre-bid walk-throughs.
3. Site Visits to the Building can be made by appointment. No biddable information will be given at those site visits.
4. Bids will be accepted until 3:00 PM on Thursday, February 28, 2023 at the District offices, 285 Blair Ave. Bids shall be enclosed in an opaque, sealed envelope, bearing the name and address of the bidder and addressed to the Owner. Mark lower left corner of the envelope "**STEM Building Art Classroom**". Bids may be electronically submitted, but this must be approved at least 72 hours in advance by written request submitted to Fred Woods, Superintendent of SJISD at fredwoods@sjisd.org. Bidders are encouraged to call ahead to be certain of hours for in-person submission, (360) 378-4133.

C. SPECIFICATIONS

1. 32 31 70 Chain Link Fences and Gates: **ADD** this section in its entirety with the attached specification section.

D. DRAWINGS

1. None

E. SUBSTITUTION REQUEST APPROVALS

<u>SECTION</u>	<u>DESCRIPTION</u>	<u>MANUFACTURER</u>
----------------	--------------------	---------------------

F. ATTACHMENTS

1. 32 31 70 Chain Link Fences and Gates
2. Plan Holders List

END OF ADDENDUM

SECTION 32 31 70
CHAIN LINK FENCING AND GATES

PART 1 - GENERAL

1.1 DESCRIPTION

- A. The Work under this Section consists of providing all operations pertaining to construction of chain link fencing and gates.

1.2 REFERENCES

- A. American Society for Testing and Materials (ASTM).
 - 1. A 491- "Specifications for Aluminum-Coated Steel Chain-Link Fence Fabric."
 - 2. F 1083 - "Specification for Pipe, Steel Black and Hot-Dipped Zinc-Coated (galvanized) welded and Seamless, for Fence Structures."

1.3 SUBMITTALS

- A. Product Data: Provide manufacturer's catalog cuts with specifications and installation instructions.
- B. Shop Drawings:
 - 1. Supply shop drawings showing the relationship of operating systems with components, including details of all major components.
 - 2. Include height and post spacing dimensions.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Builders Fence Company, Inc., Cyclone Fence, Anchor Fence, Inc., or approved.

2.2 MATERIALS

- A. Fabric: 9-gauge galvanized wire, 2-inch mesh, knuckled at both selvages.
- B. Fence Posts and Rails: Tube Steel, as shown, galvanized.
- C. Gate Frame: Tube Steel, galvanized. 3" dia. Min., or as per mfr.
- D. Tension Bars: 1/4"x3/4" galvanized steel flat bar. Bolt to mounting tabs on tube steel posts and rails. Horizontal and vertical.
- E. Tie Wire: 11-gauge galvanized steel.
- F. Fittings: Manufacturer's standard galvanized pressed steel.
- G. Bolts & Nuts: Hot dipped galvanized. Nuts are to be aluminum tamper-proof breakaway nuts.

- H. Swinging Gate Hardware:
 - 1. Double-leaf gate hardware: By fence manufacturer
 - a. Fork type latch with gravity drop, center gate-stop and drop-rod between both gate leaves. Three (3) 180-degree gate hinges per leaf. Latch to accommodate owner provided padlock.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install fences and gates in accordance with manufacturer's instruction and reviewed shop drawings.
- B. Attachment: Drilled in expansion sleeve bolts. Drill into existing slab per mfr. recommendations. Do not drill through existing slab.
- C. Space line posts as shown.
- D. Fabric tie wire only where approved.

END OF SECTION

HKP ARCHITECTS, PLLC.
204 WEST MONTGOMERY STREET
MOUNT VERNON, WA 98273
(360) 336-2155

PAGE 1 OF 2

2022- 679 SAN JUAN ISLAND SCHOOL DISTRICT #149
STEM BUILDING ART CLASSROOM
FRIDAY HARBOR HIGH SCHOOL
FRIDAY HARBOR, WA

PLAN HOLDERS LIST

COST PER SET - \$100

BID RECEIVED DATE: PRIOR TO 3:00 P.M., TUESDAY, FEBRUARY 28, 2023

NAME & ADDRESS	CONTACT	ELEC. SET	SET NO.'S	DEP. REC.	SETS RET	DEP RET
San Juan Island School District No. 149 285 Blair Avenue, P.O. Box 458 Friday Harbor, WA 98250	(360) 378-4133 www.sjisd.wednet.edu	X 1/31				
HKP Architects 204 West Montgomery Street Mount Vernon, WA 98273 Attn: Brian Poppe	(360) 336-2155 bpoppe@hkpa.com	X 1/31				
iSqft 3825 Edwards Rd, #801 Cincinnati, OH 45209	(877) 753-7043 Oregon-Washington@isqft.com	X 1/31				
Construct Connect 232 W 5th Ave. Eugene, OR 97401 Attn: John Fermiza	(541) 684-4665 www.constructconnect.com content@constructconnect.com	X 1/31				
Builders Exchange of Washington, Inc 2607 Wetmore Avenue Everett, WA 98201 Attn: Rich Morgan	(425) 258-1303 production@bxwa.com	X 1/31				
WCR Plan Center Western Construction Resources 2215 Midway Lane, Suite 208 Bellingham, WA 98226 Attn: Dawn Harju	(360) 738-0370 info@wcrinc.com www.wcrinc.com	X 1/31				
Hi Mark Construction inc. P.O. Box 756 Stanwood, WA 98292 Attn: Michelle Waterman	(253) 377-4594 mh20man@msn.com	X 2/2				

PAGE 2 OF 2

PLAN HOLDERS LIST

COST PER SET - \$100

BID RECEIVED DATE: PRIOR TO 3:00 P.M., TUESDAY, FEBRUARY 28, 2023

[illegible]